BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/08/2012-13 Dated: 13-12-2013

APPROVED TENDER SCHEDULE –'B'

Item No: 66

Name of Work: -Providing and fixing steel name boardds in attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M TAIYUB AHMED	
				Rate	Rate in Words
1	KSRB 2-2.2:Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead uplo 50m, after breaking of clods complete as per specifications Specification	Cum	14.69	208.00	Rupees two hundred only
2	KSRB 4-1.3:Providing and layingin position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications. Specification	Cum	3.67	3926.00	Rupees three thousand nine hundred twenty six only
3	KSRB 4-1.6:Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal, coarse aggregate @0.878cum and fine aggregate @0..459 cummachine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	11.02	4372.00	Rupees four thousand three hundred seventy two only
4	Supplying of M.S.Steel boards as per approved design and specification complete with all lead and lifts as per the direction of Engineer (Approved data rate)	Each	136.00	4700.00	Rupees four thousand seven hundred only
5	KSRB 15-18.2:Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade fter cleaningoil, brease, dirt andother foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	248.19	70.00	Rupees seventy only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M TAIYUB AHMED	
				Rate	Rate in Words
6	KSRRB M800-10, Painting new letters and figures of any shade with synthetic enamel paint black or any other approved color to give an even shade complete as per specifications.English and Roman-Hyphen and the like not tobe measured and paid for MORTH Specification No.801	Cum	20400	0.32	paise thirty two only
7	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	Cum	14.69	86.00	Rupees eighty six only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.